


STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT <input type="checkbox"/>				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER GMBU Q-19-8-18				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT EIGHT MILE FLAT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME GMBU (GRRV)				
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825				
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcrozier@newfield.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU-36846			11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		690 FSL 690 FWL		SWSW	19	8.0 S	18.0 E	S		
Top of Uppermost Producing Zone		1061 FSL 1053 FWL		SWSW	19	8.0 S	18.0 E	S		
At Total Depth		1427 FSL 1435 FWL		NESW	19	8.0 S	18.0 E	S		
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 1427			23. NUMBER OF ACRES IN DRILLING UNIT 20				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 1145			26. PROPOSED DEPTH MD: 6498 TVD: 6400				
27. ELEVATION - GROUND LEVEL 5031			28. BOND NUMBER WYB000493			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
Surf	12.25	8.625	0 - 300	24.0	J-55 ST&C	8.3	Class G	138	1.17	15.8
Prod	7.875	5.5	0 - 6498	15.5	J-55 LT&C	8.3	Premium Lite High Strength	311	3.26	11.0
							50/50 Poz	363	1.24	14.3
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Mandie Crozier				TITLE Regulatory Tech			PHONE 435 646-4825			
SIGNATURE				DATE 10/31/2012			EMAIL mcrozier@newfield.com			
API NUMBER ASSIGNED 43047532940000				APPROVAL  Permit Manager						

NEWFIELD PRODUCTION COMPANY
GMBU Q-19-8-18
AT SURFACE: SW/SW (LOT #6) SECTION 19, T8S R18E
UINTAH COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0' – 1895'
Green River	1895'
Wasatch	6625'
Proposed TD	6498'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation (Oil) 1895' – 6625'

Fresh water may be encountered in the Uinta Formation, but would not be expected below about 350'. All water shows and water bearing geologic units shall be reported to the geologic and engineering staff of the Vernal Office prior to running the next string of casing or before plugging orders are requested. All water shows must be reported within one (1) business day after being encountered.

All usable (<10,000 PPM TDS) water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling will be recorded by depth and adequately protected. This information shall be reported to the Vernal Office.

Detected water flows shall be sampled, analyzed, and reported to the geologic & engineering staff of the Vernal Office. The office may request additional water samples for further analysis. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required.

The following information is requested for water shows and samples where applicable:

Location & Sampled Interval	Date Sampled
Flow Rate	Temperature
Hardness	pH
Water Classification (State of Utah)	Dissolved Calcium (Ca) (mg/l)
Dissolved Iron (Fe) (ug/l)	Dissolved Sodium (Na) (mg/l)
Dissolved Magnesium (Mg) (mg/l)	Dissolved Carbonate (CO ₃) (mg/l)
Dissolved Bicarbonate (NaHCO ₃) (mg/l)	Dissolved Chloride (Cl) (mg/l)
Dissolved Sulfate (SO ₄) (mg/l)	Dissolved Total Solids (TDS) (mg/l)

4. **PROPOSED CASING PROGRAM**

a. Casing Design: GMBU Q-19-8-18

Size	Interval		Weight	Grade	Coupling	Design Factors		
	Top	Bottom				Burst	Collapse	Tension
Surface casing 8-5/8"	0'	300'	24.0	J-55	STC	2,950 17.53	1,370 14.35	244,000 33.89
Prod casing 5-1/2"	0'	6,498'	15.5	J-55	LTC	4,810 2.33	4,040 1.95	217,000 2.15

Assumptions:

- 1) Surface casing max anticipated surface press (MASP) = Frac gradient – gas gradient
- 2) Prod casing MASP (production mode) = Pore pressure – gas gradient
- 3) All collapse calculations assume fully evacuated casing w/ gas gradient
- 4) All tension calculations assume air weight

Frac gradient at surface casing shoe = 13.0 ppg
 Pore pressure at surface casing shoe = 8.33 ppg
 Pore pressure at prod casing shoe = 8.33 ppg
 Gas gradient = 0.115 psi/ft

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of 1 (one) centralizer on each of the bottom three (3) joints.

b. Cementing Design: GMBU Q-19-8-18

Job	Fill	Description	Sacks	OH Excess*	Weight (ppg)	Yield (ft ³ /sk)
			ft ³			
Surface casing	300'	Class G w/ 2% CaCl	138 161	30%	15.8	1.17
Prod casing Lead	4,498'	Prem Lite II w/ 10% gel + 3% KCl	311 1013	30%	11.0	3.26
Prod casing Tail	2,000'	50/50 Poz w/ 2% gel + 3% KCl	363 451	30%	14.3	1.24

*Actual volume pumped will be 15% over the caliper log

- Compressive strength of lead cement: 1800 psi @ 24 hours, 2250 psi @ 72 hours
- Compressive strength of tail cement: 2500 psi @ 24 hours

Hole Sizes: A 12-1/4" hole will be drilled for the 8-5/8" surface casing. A 7-7/8" hole will be drilled for the 5-1/2" production casing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

From surface to ± 300 feet will be drilled with an air/mist system. The air rig is equipped with a 6 1/2" blooie line that is straight run and securely anchored. The blooie line is used with a discharge less than 100 ft from the wellbore in order to minimize the well pad size. The blooie line is not equipped with an automatic igniter or continuous pilot light and the compressor is located less than 100 ft from the well bore due to the low possibility of combustion with the air dust mixture. The trailer mounted compressor (capacity of 2000 CFM) has a safety shut-off valve which is located 15 feet from the air rig. A truck with 70 bbls of water is on stand by to be used as kill fluid, if necessary. From about ± 300 feet to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCl substitute additive. This additive will be identified in the APD and reviewed to determine if the reserve pit shall be lined. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior BLM approval to ensure adequate protection of fresh aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

Newfield Production will **visually** monitor pit levels and flow from the well during drilling operations.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 300' +/-, and a Compensated Neutron-Formation Density Log from TD to 3500' +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous drilling in the area at this depth. Maximum anticipated

bottomhole pressure will approximately equal total depth in feet multiplied by a 0.433 psi/foot gradient.


10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the first quarter of 2013, and take approximately seven (7) days from spud to rig release.

T8S, R18E, S.L.B.&M.**NEWFIELD EXPLORATION COMPANY****WELL LOCATION:****Q-19-8-18**ELEV. UNGRADED GROUND = 5031'


WELL LOCATION, Q-19-8-18, LOCATED AS SHOWN IN THE SW 1/4 SW 1/4 (Lot 6) OF SECTION 19, T8S, R18E, S.L.B.&M. UTAH COUNTY, UTAH.

TARGET BOTTOM HOLE, Q-19-8-18, LOCATED AS SHOWN IN THE NE 1/4 SW 1/4 OF SECTION 19, T8S, R18E, S.L.B.&M. UTAH COUNTY, UTAH.

**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.



R R
17 18
W E



= SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'

NAD 83 (SURFACE LOCATION)	NAD 83 (BOTTOM HOLE LOCATION)
LATITUDE = 40°05'53.21"	LATITUDE = 40°06'00.50"
LONGITUDE = 109°56'34.72"	LONGITUDE = 109°56'25.12"
NAD 27 (SURFACE LOCATION)	NAD 27 (BOTTOM HOLE LOCATION)
LATITUDE = 40°05'53.35"	LATITUDE = 40°06'00.63"
LONGITUDE = 109°56'32.19"	LONGITUDE = 109°56'22.59"


TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 02-15-12	SURVEYED BY: C.S.	VERSION:
DATE DRAWN: 10-01-12	DRAWN BY: V.H.	V2
REVISED:	SCALE: 1" = 1000'	

RECEIVED: October 31, 2012

Access Road Map



Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
 F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

13-19-8-18 (Existing Well)
 Q-19-8-18 (Proposed Well)
 A-25-8-17 (Proposed Well)

SEC. 19, T8S, R18E, S.L.B.&M. Uintah County, UT.


DRAWN BY:	A.P.C.	REVISED:	VERSION:
DATE:	10-01-2012		V2
SCALE:	1:100,000		

TOPOGRAPHIC MAP

SHEET

A

Access Road Map



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

13-19-8-18 (Existing Well)
Q-19-8-18 (Proposed Well)
A-25-8-17 (Proposed Well)
SEC. 19, T8S, R18E, S.L.B.&M. Uintah County, UT.


DRAWN BY:	A.P.C.	REVISED:	10-01-12 A.P.C.	VERSION:
DATE:	02-27-2012			V2
SCALE:	1" = 2,000'			

TOPOGRAPHIC MAP

SHEET

B

Proposed Pipeline Map



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

13-19-8-18 (Existing Well)
Q-19-8-18 (Proposed Well)
A-25-8-17 (Proposed Well)
SEC. 19, T8S, R18E, S.L.B.&M. Uintah County, UT.

DRAWN BY:	A.P.C.	REVISED:	10-01-12 A.P.C.	VERSION:
DATE:	02-27-2012			V2
SCALE:	1" = 2,000'			


TOPOGRAPHIC MAP

SHEET

C

Exhibit "B" Map

13-19-8-18 (Existing Well)
 Q-19-8-18 (Proposed Well)
 A-25-8-17 (Proposed Well)



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
 F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

13-19-8-18 (Existing Well)
 Q-19-8-18 (Proposed Well)
 A-25-8-17 (Proposed Well)
 SEC. 19, T8S, R18E, S.L.B.&M. Uintah County, UT.

DRAWN BY:	A.P.C.	REVISED:	VERSION:
DATE:	10-01-2012		V2
SCALE:	1" = 2,000'		

TOPOGRAPHIC MAP

SHEET

D



NEWFIELD EXPLORATION

**USGS Myton SW (UT)
SECTION 19 T8S R18E
Q-19-8-18**

Wellbore #1

Plan: Design #1

Standard Planning Report

24 September, 2012





Payzone Directional Planning Report



Database:	EDM 2003.21 Single User Db	Local Co-ordinate Reference:	Well Q-19-8-18
Company:	NEWFIELD EXPLORATION	TVD Reference:	Q-19-8-18 @ 5043.0ft (Original Well Elev)
Project:	USGS Myton SW (UT)	MD Reference:	Q-19-8-18 @ 5043.0ft (Original Well Elev)
Site:	SECTION 19 T8S R18E	North Reference:	True
Well:	Q-19-8-18	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site		SECTION 19 T8S R18E, SEC 19 T8S R18E			
Site Position:		Northing:	7,209,998.99 ft	Latitude:	40° 6' 10.109 N
From:	Lat/Long	Easting:	2,078,000.00 ft	Longitude:	109° 56' 7.952 W
Position Uncertainty:	0.0 ft	Slot Radius:	"	Grid Convergence:	1.00 °

Well	Q-19-8-18, SHL LAT: 40 05 53.21 LONG: -109 56 34.72					
Well Position	+N/-S	-1,710.0 ft	Northing:	7,208,253.07 ft	Latitude:	40° 5' 53.210 N
	+E/-W	-2,079.8 ft	Easting:	2,075,950.24 ft	Longitude:	109° 56' 34.720 W
Position Uncertainty		0.0 ft	Wellhead Elevation:	5,043.0 ft	Ground Level:	5,031.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	9/24/2012	11.11	65.83	52,194

Design	Design #1				
Audit Notes:					
Version:	Phase:	PROTOTYPE		Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	5,450.0	0.0	0.0	44.34	

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,328.3	10.93	44.34	1,323.9	49.5	48.4	1.50	1.50	0.00	44.34	
5,530.6	10.93	44.34	5,450.0	619.1	605.1	0.00	0.00	0.00	0.00	Q-19-8-18 TGT
6,498.1	10.93	44.34	6,400.0	750.2	733.2	0.00	0.00	0.00	0.00	



Payzone Directional

Planning Report



Database:	EDM 2003.21 Single User Db	Local Co-ordinate Reference:	Well Q-19-8-18
Company:	NEWFIELD EXPLORATION	TVD Reference:	Q-19-8-18 @ 5043.0ft (Original Well Elev)
Project:	USGS Myton SW (UT)	MD Reference:	Q-19-8-18 @ 5043.0ft (Original Well Elev)
Site:	SECTION 19 T8S R18E	North Reference:	True
Well:	Q-19-8-18	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	1.50	44.34	700.0	0.9	0.9	1.3	1.50	1.50	0.00
800.0	3.00	44.34	799.9	3.7	3.7	5.2	1.50	1.50	0.00
900.0	4.50	44.34	899.7	8.4	8.2	11.8	1.50	1.50	0.00
1,000.0	6.00	44.34	999.3	15.0	14.6	20.9	1.50	1.50	0.00
1,100.0	7.50	44.34	1,098.6	23.4	22.8	32.7	1.50	1.50	0.00
1,200.0	9.00	44.34	1,197.5	33.6	32.9	47.0	1.50	1.50	0.00
1,300.0	10.50	44.34	1,296.1	45.7	44.7	64.0	1.50	1.50	0.00
1,328.3	10.93	44.34	1,323.9	49.5	48.4	69.2	1.50	1.50	0.00
1,400.0	10.93	44.34	1,394.3	59.2	57.9	82.8	0.00	0.00	0.00
1,500.0	10.93	44.34	1,492.5	72.8	71.1	101.8	0.00	0.00	0.00
1,600.0	10.93	44.34	1,590.7	86.3	84.4	120.7	0.00	0.00	0.00
1,700.0	10.93	44.34	1,688.9	99.9	97.6	139.7	0.00	0.00	0.00
1,800.0	10.93	44.34	1,787.0	113.4	110.9	158.6	0.00	0.00	0.00
1,900.0	10.93	44.34	1,885.2	127.0	124.1	177.6	0.00	0.00	0.00
2,000.0	10.93	44.34	1,983.4	140.5	137.4	196.5	0.00	0.00	0.00
2,100.0	10.93	44.34	2,081.6	154.1	150.6	215.5	0.00	0.00	0.00
2,200.0	10.93	44.34	2,179.8	167.7	163.9	234.4	0.00	0.00	0.00
2,300.0	10.93	44.34	2,278.0	181.2	177.1	253.4	0.00	0.00	0.00
2,400.0	10.93	44.34	2,376.2	194.8	190.4	272.3	0.00	0.00	0.00
2,500.0	10.93	44.34	2,474.4	208.3	203.6	291.3	0.00	0.00	0.00
2,600.0	10.93	44.34	2,572.5	221.9	216.9	310.2	0.00	0.00	0.00
2,700.0	10.93	44.34	2,670.7	235.4	230.1	329.2	0.00	0.00	0.00
2,800.0	10.93	44.34	2,768.9	249.0	243.3	348.1	0.00	0.00	0.00
2,900.0	10.93	44.34	2,867.1	262.5	256.6	367.1	0.00	0.00	0.00
3,000.0	10.93	44.34	2,965.3	276.1	269.8	386.1	0.00	0.00	0.00
3,100.0	10.93	44.34	3,063.5	289.6	283.1	405.0	0.00	0.00	0.00
3,200.0	10.93	44.34	3,161.7	303.2	296.3	424.0	0.00	0.00	0.00
3,300.0	10.93	44.34	3,259.9	316.7	309.6	442.9	0.00	0.00	0.00
3,400.0	10.93	44.34	3,358.0	330.3	322.8	461.9	0.00	0.00	0.00
3,500.0	10.93	44.34	3,456.2	343.9	336.1	480.8	0.00	0.00	0.00
3,600.0	10.93	44.34	3,554.4	357.4	349.3	499.8	0.00	0.00	0.00
3,700.0	10.93	44.34	3,652.6	371.0	362.6	518.7	0.00	0.00	0.00
3,800.0	10.93	44.34	3,750.8	384.5	375.8	537.7	0.00	0.00	0.00
3,900.0	10.93	44.34	3,849.0	398.1	389.1	556.6	0.00	0.00	0.00
4,000.0	10.93	44.34	3,947.2	411.6	402.3	575.6	0.00	0.00	0.00
4,100.0	10.93	44.34	4,045.4	425.2	415.6	594.5	0.00	0.00	0.00
4,200.0	10.93	44.34	4,143.5	438.7	428.8	613.5	0.00	0.00	0.00
4,300.0	10.93	44.34	4,241.7	452.3	442.1	632.4	0.00	0.00	0.00
4,400.0	10.93	44.34	4,339.9	465.8	455.3	651.4	0.00	0.00	0.00
4,500.0	10.93	44.34	4,438.1	479.4	468.6	670.3	0.00	0.00	0.00
4,600.0	10.93	44.34	4,536.3	492.9	481.8	689.3	0.00	0.00	0.00
4,700.0	10.93	44.34	4,634.5	506.5	495.0	708.2	0.00	0.00	0.00
4,800.0	10.93	44.34	4,732.7	520.1	508.3	727.2	0.00	0.00	0.00
4,900.0	10.93	44.34	4,830.9	533.6	521.5	746.2	0.00	0.00	0.00
5,000.0	10.93	44.34	4,929.0	547.2	534.8	765.1	0.00	0.00	0.00
5,100.0	10.93	44.34	5,027.2	560.7	548.0	784.1	0.00	0.00	0.00
5,200.0	10.93	44.34	5,125.4	574.3	561.3	803.0	0.00	0.00	0.00



Payzone Directional

Planning Report




Database:	EDM 2003.21 Single User Db	Local Co-ordinate Reference:	Well Q-19-8-18
Company:	NEWFIELD EXPLORATION	TVD Reference:	Q-19-8-18 @ 5043.0ft (Original Well Elev)
Project:	USGS Myton SW (UT)	MD Reference:	Q-19-8-18 @ 5043.0ft (Original Well Elev)
Site:	SECTION 19 T8S R18E	North Reference:	True
Well:	Q-19-8-18	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,300.0	10.93	44.34	5,223.6	587.8	574.5	822.0	0.00	0.00	0.00
5,400.0	10.93	44.34	5,321.8	601.4	587.8	840.9	0.00	0.00	0.00
5,500.0	10.93	44.34	5,420.0	614.9	601.0	859.9	0.00	0.00	0.00
5,530.6	10.93	44.34	5,450.0	619.1	605.1	865.7	0.00	0.00	0.00
5,600.0	10.93	44.34	5,518.2	628.5	614.3	878.8	0.00	0.00	0.00
5,700.0	10.93	44.34	5,616.4	642.0	627.5	897.8	0.00	0.00	0.00
5,800.0	10.93	44.34	5,714.5	655.6	640.8	916.7	0.00	0.00	0.00
5,900.0	10.93	44.34	5,812.7	669.1	654.0	935.7	0.00	0.00	0.00
6,000.0	10.93	44.34	5,910.9	682.7	667.3	954.6	0.00	0.00	0.00
6,100.0	10.93	44.34	6,009.1	696.3	680.5	973.6	0.00	0.00	0.00
6,200.0	10.93	44.34	6,107.3	709.8	693.8	992.5	0.00	0.00	0.00
6,300.0	10.93	44.34	6,205.5	723.4	707.0	1,011.5	0.00	0.00	0.00
6,400.0	10.93	44.34	6,303.7	736.9	720.3	1,030.4	0.00	0.00	0.00
6,498.1	10.93	44.34	6,400.0	750.2	733.2	1,049.0	0.00	0.00	0.00

API Well Number: 43047532940000





Project: USGS Myton SW (UT)
 Site: SECTION 19 T8S R18E
 Well: Q-19-8-18
 Wellbore: Wellbore #1
 Design: Design #1



Azimuths to True North
 Magnetic North: 11.11°

Magnetic Field
 Strength: 52193.5snT
 Dip Angle: 65.83°
 Date: 9/24/2012
 Model: IGRF2010



WELLBORE TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Shape
Q-19-8-18 TGT	5450.0	619.1	605.1	Circle (Radius: 75.0)

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	600.0	0.00	0.00	600.0	0.0	0.0	0.00	0.00	0.0	
3	1328.3	10.93	44.34	1323.9	49.5	48.4	1.50	44.34	69.2	
4	5530.6	10.93	44.34	5450.0	619.1	605.1	0.00	0.00	865.7	Q-19-8-18 TGT
5	6498.1	10.93	44.34	6400.0	750.2	733.2	0.00	0.00	1049.0	



**NEWFIELD PRODUCTION COMPANY
GMBU Q-19-8-18
AT SURFACE: SW/SW (LOT #6) SECTION 19, T8S R18E
UINTAH COUNTY, UTAH**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Newfield Production Company well location site GMBU Q-19-8-18 located in the SW 1/4 SW 1/4 Section 19, T8S, R18E, Uintah County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 – 1.4 miles \pm to the junction of this highway and UT State Hwy 53; proceed in a southeasterly direction – 6.8 miles \pm to it's junction with an existing road to the east; proceed in a easterly direction – 6.6 miles \pm to it's junction with the beginning of the access road to the existing 13-19-8-18 well location.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal. Any necessary fill material for repair will be purchase and hauled from private sources.

2. PLANNED ACCESS ROAD

There is no proposed access road for this location. The proposed well will be drilled directionally off of the existing 13-19-8-18 well pad. See attached **Topographic Map "B"**.

There will be **no** culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. LOCATION OF EXISTING WELLS

Refer to Exhibit "B".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

There are no existing facilities that will be used by this well.

It is anticipated that this well will be a producing oil well.

Upon construction of a tank battery, the well pad will be surrounded by a dike of sufficient capacity to contain at minimum 110% of the largest tank volume within the facility battery.

Tank batteries will be built to State specifications.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted a flat, non-reflective, earth tone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Newfield Production will transport water by truck from nearest water source as determined by a Newfield representative for the purpose of drilling the above mentioned well. The available water sources are as follows:

Johnson Water District
Water Right : 43-10136

Maurice Harvey Pond
Water Right: 47-1358

Neil Moon Pond
Water Right: 43-11787

Newfield Collector Well
Water Right: 47-1817 (A30414DVA, contracted with the Duchesne County Conservancy District).

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Newfield requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

8. **ANCILLARY FACILITIES**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Existing fences to be crossed by the access road will be braced and tied off before cutting so as to prevent slacking in the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM specifications.

10. **PLANS FOR RESTORATION OF SURFACE:**

- a) Producing Location

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

- b) Dry Hole Abandoned Location

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP** – Buruea of Land Management.

12. **OTHER ADDITIONAL INFORMATION**

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. State of Utah Antiquities Project Permit # U-04-MQ-1430b 1/4/05, prepared by Montgomery Archaeological Consultants. . Paleontological Resource Survey prepared by, Wade Miller, 9/27/04. See attached report cover pages, Exhibit "D".

Surface Flow Line

Newfield requests 1,730' of surface flow line be granted. The Surface Flow Line will consist of up to a 14" bundled pipe consisting of 2-2" poly glycol lines and 1-3" production line. Refer to Topographic Map "C" for the proposed location of the proposed flow line. Flow lines will be tan and will be constructed using the following procedures as outlined in the Greater Monument Butte Green River Development SOP.

Water Disposal

After first production, if the production water meets quality guidelines, it will be transported to the Ashley, Monument Butte, Jonah, South Wells Draw and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project. Water not meeting quality criteria, will be disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E), Federally approved surface disposal facilities or at a State of Utah approved surface disposal facilities.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Details of the On-Site Inspection

The proposed GMBU Q-19-8-18 was on-sited on 9/18/12. The following were present; Corie Miller (Newfield Production) and Sheri Wysong (Bureau of Land Management).

Hazardous Material Declaration

Newfield Production Company guarantees that during the drilling and completion of the GMBU Q-19-8-18, Newfield will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Newfield also guarantees that during the drilling and completion of the GMBU Q-19-8-18, Newfield will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Newfield Production Company or a contractor employed by Newfield Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

13. LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:

Representative

Name: Corie Miller
Address: Newfield Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that NEWFIELD PRODUCTION COMPANY is considered to be the operator of well #Q-19-8-18, Section 19, Township 8S, Range 18E: Lease UTU-36846 Uintah County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by, Federal Bond #WYB000493.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Newfield Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.

10/31/12
Date

Mandie Crozier
Regulatory Analyst
Newfield Production Company

Typical 2M BOP stack configuration



2M CHOKE MANIFOLD EQUIPMENT - CONFIGURATION OF CHOKES MAY VARY

NEWFIELD EXPLORATION COMPANY

WELL PAD INTERFERENCE PLAT

TOP HOLE FOOTAGES

Q-19-8-18 (PROPOSED)
690' FSL & 690' FWL

A-25-8-17 (PROPOSED)
703' FSL & 674' FWL

CENTER OF PATTERN FOOTAGES

Q-19-8-18 (PROPOSED)
1298' FSL & 1305' FWL


A-25-8-17 (PROPOSED)
0' FSL & 0' FWL

BOTTOM HOLE FOOTAGES

Q-19-8-18 (PROPOSED)
1427' FSL & 1435' FWL

A-25-8-17 (PROPOSED)
165' FNL & 157' FEL

13-19-8-18 (Existing Well)
Q-19-8-18 (Proposed Well)
A-25-8-17 (Proposed Well)
Pad Location: SWSW (Lot 6) Section 19, T8S, R18E, S.L.B.&M.



RELATIVE COORDINATES From Top Hole to C.O.P.

WELL	NORTH	EAST
Q-19-8-18	619'	605'
A-25-8-17	-714'	-662'

LATITUDE & LONGITUDE Surface position of Wells (NAD 83)

WELL	LATITUDE	LONGITUDE
13-19-8-18	40° 05' 53.08"	109° 56' 34.51"
Q-19-8-18	40° 05' 53.21"	109° 56' 34.72"
A-25-8-17	40° 05' 53.34"	109° 56' 34.93"

LATITUDE & LONGITUDE Bottom Hole Position (NAD 83)



WELL	LATITUDE	LONGITUDE
Q-19-8-18	40° 06' 00.50"	109° 56' 25.12"
A-25-8-17	40° 05' 44.78"	109° 56' 45.64"

RELATIVE COORDINATES From Top Hole to Bottom Hole

WELL	NORTH	EAST
Q-19-8-18	750'	733'
A-25-8-17	-881'	-817'

SURVEYED BY: C.S. DATE SURVEYED: 02-15-12 VERSION:
DRAWN BY: V.H. DATE DRAWN: 10-01-12
SCALE: 1" = 60' REVISED: V2

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078





NEWFIELD EXPLORATION COMPANY**LOCATION LAYOUT****13-19-8-18 (Existing Well)****Q-19-8-18 (Proposed Well)****A-25-8-17 (Proposed Well)****Pad Location: SWSW (Lot 6) Section 19, T8S, R18E, S.L.B.&M.****NOTE:**

The topsoil & excess material areas are calculated as being mounds containing 3,000 cubic yards of dirt (a 10% fluff factor is included). The mound areas are calculated with push slopes of 1.5:1 & fall slopes of 1.5:1.

SURVEYED BY: C.S.	DATE SURVEYED: 02-15-12	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 02-16-12	V2
SCALE: 1" = 60'	REVISED: V.H. 10-01-12	

Tri State
Land Surveying, Inc.
(435) 781-2501
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: October 31, 2012

NEWFIELD EXPLORATION COMPANY***CROSS SECTIONS******13-19-8-18 (Existing Well)******Q-19-8-18 (Proposed Well)******A-25-8-17 (Proposed Well)****Pad Location: SWSW (Lot 6) Section 19, T8S, R18E, S.L.B.&M.*

NOTE:
UNLESS OTHERWISE
NOTED ALL CUT/FILL
SLOPES ARE AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES
(No Shrink or swell adjustments have been used)
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	1,670	0	Topsoil is not included in Pad Cut	1,670
PIT	690	0		690
TOTALS	2,360	0	360	2,360

SURVEYED BY: C.S.	DATE SURVEYED: 02-15-12	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 02-16-12	V2
SCALE: 1" = 60'	REVISED: V.H. 10-01-12	

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078
(435) 781-2501

RECEIVED: October 31, 2012

NEWFIELD EXPLORATION COMPANY



TYPICAL RIG LAYOUT

13-19-8-18 (Existing Well)

Q-19-8-18 (Proposed Well)

A-25-8-17 (Proposed Well)

Pad Location: SWSW (Lot 6) Section 19, T8S, R18E, S.L.B.&M.




Note:
Flare pit is to be located a Minimum of 100' from the Proposed Well Head.

SURVEYED BY: C.S.	DATE SURVEYED: 02-15-12	VERSION:
DRAWN BY: M.W.	DATE DRAWN: 02-16-12	V2
SCALE: 1" = 60'	REVISED: V.H. 10-01-12	

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078
(435) 781-2501

RECEIVED: October 31, 2012

NEWFIELD EXPLORATION COMPANY***RECLAMATION LAYOUT******13-19-8-18 (Existing Well)******Q-19-8-18 (Proposed Well)******A-25-8-17 (Proposed Well)******Pad Location: SWSW (Lot6) Section 19, T8S, R18E, S.L.B.&M.*****Notes:**

1. Reclaimed Area to Include Seeding of Approved Vegetation and Sufficient Storm Water Management System.
2. Actual Equipment Layout and Reclaimed Pad Surface Area May Change due to Production Requirements or Site Conditions.


DISTURBED AREA:

TOTAL DISTURBED AREA = 2.73 ACRES
 TOTAL RECLAIMED AREA = 2.03 ACRES
 UNRECLAIMED AREA = 0.70 ACRES

SURVEYED BY: C.S.	DATE SURVEYED: 02-15-12	VERSION:
DRAWN BY: V.H.	DATE DRAWN: 10-01-12	V2
SCALE: 1" = 60'	REVISED:	

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: October 31, 2012

NEWFIELD EXPLORATION COMPANY*PROPOSED SITE FACILITY DIAGRAM***13-19-8-18 (Existing Well) UTU-36846****Q-19-8-18 (Proposed Well) UTU-36846****A-25-8-17 (Proposed Well) UTU-74870***Pad Location: SWSW (Lot 6) Section 19, T8S, R18E, S.L.B.&M.
Uintah County, Utah****Legend***


Emulsion Line
 Load Rack - - - - -
 Water Line - . - . -
 Gas Sales - . . - . -
 Oil Line - - - - -

NOT TO SCALE

SURVEYED BY: C.S.	DATE SURVEYED: 02-15-12	VERSION:
DRAWN BY: V.H.	DATE DRAWN: 10-01-12	V2
SCALE: NONE	REVISED:	



Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: October 31, 2012



API Number: 4304753294
Well Name: GMBU Q-19-8-18
Township T08.0S Range R18.0E Section 19
Meridian: SLBM
Operator: NEWFIELD PRODUCTION COMPANY

Map Prepared:
 Map Produced by Diana Mason



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

November 5, 2012

Memorandum

To: Assistant Field Manager Minerals, Vernal Field Office

From: Michael Coulthard, Petroleum Engineer

Subject: 2012 Plan of Development Greater Monument
Butte Unit, Duchesne and Uintah Counties,
Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2012 within the Greater Monument Butte Unit, Duchesne and Uintah Counties, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ GREEN RIVER)		
43-047-53287	GMBU D-26-8-17	Sec 26 T08S R17E 0470 FNL 1913 FWL BHL Sec 26 T08S R17E 0022 FNL 1165 FWL
43-013-51824	GMBU J-33-8-17	Sec 34 T08S R17E 1925 FNL 0723 FWL BHL Sec 33 T08S R17E 1158 FNL 0127 FEL
43-047-53288	GMBU H-26-8-17	Sec 26 T08S R17E 0461 FNL 1931 FWL BHL Sec 26 T08S R17E 1325 FNL 2593 FEL
43-013-51825	GMBU G-34-8-17	Sec 34 T08S R17E 1905 FNL 0730 FWL BHL Sec 34 T08S R17E 1171 FNL 1452 FWL
43-013-51826	GMBU L-34-8-17	Sec 34 T08S R17E 1994 FNL 1974 FEL BHL Sec 34 T08S R17E 2488 FSL 1205 FEL
43-013-51827	GMBU I-34-8-17	Sec 34 T08S R17E 1978 FNL 1960 FEL BHL Sec 34 T08S R17E 1036 FNL 1149 FEL
43-013-51828	GMBU J-34-8-17	Sec 35 T08S R17E 2086 FNL 0677 FWL BHL Sec 34 T08S R17E 1059 FNL 0199 FEL
43-013-51829	GMBU G-35-8-17	Sec 35 T08S R17E 2073 FNL 0694 FWL BHL Sec 35 T08S R17E 1129 FNL 1570 FWL

RECEIVED: November 06, 2012

API #	WELL NAME	LOCATION
(Proposed PZ GREEN RIVER)		
43-013-51830	GMBU Q-35-8-17	Sec 35 T08S R17E 1842 FSL 0767 FWL BHL Sec 35 T08S R17E 1108 FSL 1679 FWL
43-013-51831	GMBU N-35-8-17	Sec 35 T08S R17E 1855 FSL 0783 FWL BHL Sec 35 T08S R17E 2568 FNL 1672 FWL
43-047-53289	GMBU G-26-8-17	Sec 26 T08S R17E 2013 FNL 1770 FWL BHL Sec 26 T08S R17E 0935 FNL 1126 FWL
43-047-53290	GMBU N-26-8-17	Sec 26 T08S R17E 2031 FNL 1781 FWL BHL Sec 26 T08S R17E 2583 FSL 1179 FWL
43-013-51832	GMBU P-26-8-17	Sec 27 T08S R17E 2143 FSL 0891 FEL BHL Sec 26 T08S R17E 1001 FSL 0275 FWL
43-013-51833	GMBU O-26-8-17	Sec 27 T08S R17E 2163 FSL 0896 FEL BHL Sec 26 T08S R17E 2511 FNL 0190 FWL
43-047-53291	GMBU A-25-8-17	Sec 19 T08S R18E 0703 FSL 0674 FWL BHL Sec 25 T08S R17E 0165 FNL 0157 FEL
43-013-51834	GMBU L-27-8-17	Sec 27 T08S R17E 2249 FSL 1686 FEL BHL Sec 27 T08S R17E 2206 FNL 1161 FEL
43-013-51835	GMBU S-27-8-17	Sec 27 T08S R17E 2235 FSL 1670 FEL BHL Sec 27 T08S R17E 1160 FSL 1165 FEL
43-047-53292	GMBU R-19-8-18	Sec 19 T08S R18E 0694 FSL 2001 FEL BHL Sec 19 T08S R18E 1368 FSL 2492 FWL
43-047-53293	GMBU S-19-8-18	Sec 19 T08S R18E 0676 FSL 1990 FEL BHL Sec 19 T08S R18E 1501 FSL 1215 FEL
43-047-53294	GMBU Q-19-8-18	Sec 19 T08S R18E 0690 FSL 0690 FWL BHL Sec 19 T08S R18E 1427 FSL 1435 FWL

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard
DN: cn=Michael L. Coulthard, o=Bureau of Land Management,
ou=Branch of Minerals, email=Michael_Coulthard@blm.gov, c=US
Date: 2012.11.05 14:34:00 -0700

bcc: File - Greater Monument Butte Unit

Division of Oil Gas and Mining

Central Files

Agr. Sec. Chron

Fluid Chron

MCoulthard:mc:11-5-12

RECEIVED: November 06, 2012

VIA ELECTRONIC DELIVERY



November 6, 2012

State of Utah, Division of Oil, Gas and Mining
ATTN: Diana Mason
P.O. Box 145801
Salt Lake City, UT 84114-5801

RE: Directional Drilling
GMBU Q-19-8-18
Greater Monument Butte (Green River) Unit

Surface Hole: T8S-R18E Section 19: SWSW (Lot 6) (UTU-36846)
690' FSL 690' FWL

At Target: T8S-R18E Section 19: NESW (UTU-36846)
1427' FSL 1435' FWL

Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing by Newfield Production Company (NPC) of an Application for Permit to Drill the above referenced well dated 11/1/2012, a copy of which is attached, and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill this well.

The surface hole and target locations of this well are both within the boundaries of the Greater Monument Butte Unit (UTU-87538X), of which Newfield certifies that it is the operator. Further, Newfield certifies that all lands within 460 feet of the entire directional well bore are within the Greater Monument Butte Unit.

NPC is permitting this well as a directional well in order to mitigate surface disturbance by utilizing pre-existing roads and pipelines.

NPC hereby requests our application for permit to drill be granted pursuant to R649-3-11. If you have any questions or require further information, please contact the undersigned at 303-383-4121 or by email at lburget@newfield.com. Your consideration in this matter is greatly appreciated.

Sincerely,
Newfield Production Company

A handwritten signature in blue ink that reads "Leslie Burget".

Leslie Burget
Land Associate

Form 3160-3
(August 2007)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU36846
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator NEWFIELD PRODUCTION COMPANY Contact: MANDIE CROZIER Email: mcrozier@newfield.com		7. If Unit or CA Agreement, Name and No. GREATER MONUMENT
3a. Address ROUTE #3 BOX 3630 MYTON, UT 84052	3b. Phone No. (include area code) Ph: 435-646-4825 Fx: 435-646-3031	8. Lease Name and Well No. GMBU Q-19-8-18
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SWSW Lot 6 690FSL 690FWL At proposed prod. zone NESW 1427FSL 1435FWL		9. API Well No.
14. Distance in miles and direction from nearest town or post office* 14.9 MILES SOUTHEAST OF MYTON, UT		10. Field and Pool, or Exploratory MONUMENT BUTTE
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 1427'	16. No. of Acres in Lease 1178.60	11. Sec., T., R., M., or Blk. and Survey or Area Sec 19 T8S R18E Mer SLB
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 1145'	19. Proposed Depth 6498 MD 6400 TVD	12. County or Parish UINTAH
21. Elevations (Show whether DF, KB, RT, GL, etc.) 5031 GL	22. Approximate date work will start 03/31/2012	13. State UT
23. Estimated duration 7 DAYS		17. Spacing Unit dedicated to this well 20.00
20. BLM/BIA Bond No. on file WYB000493		

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature (Electronic Submission)	Name (Printed/Typed) MANDIE CROZIER Ph: 435-646-4825	Date 11/01/2012
Title REGULATORY ANALYST		
Approved by (Signature)	Name (Printed/Typed)	Date
Title	Office	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #157176 verified by the BLM Well Information System
For NEWFIELD PRODUCTION COMPANY, sent to the Vernal

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

API Well Number: 43047532940000

Additional Operator Remarks:

SURFACE LEASE: UTU-36846
BOTTOM HOLE LEASE: UTU-36846

T8S, R18E, S.L.B.&M.


NEWFIELD EXPLORATION COMPANY

WELL LOCATION:
Q-19-8-18

ELEV. UNGRADED GROUND = 5031'

WELL LOCATION, Q-19-8-18, LOCATED AS SHOWN IN THE SW 1/4 SW 1/4 (Lot 6) OF SECTION 19, T8S, R18E, S.L.B.&M. UINTAH COUNTY, UTAH.

TARGET BOTTOM HOLE, Q-19-8-18, LOCATED AS SHOWN IN THE NE 1/4 SW 1/4 OF SECTION 19, T8S, R18E, S.L.B.&M. UINTAH COUNTY, UTAH.



- NOTES:**
1. Well footages are measured at right angles to the Section Lines.
 2. Bearings are based on Global Positioning Satellite observations.

THIS IS TO CERTIFY THAT THE ABOVE WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

STACY W.
10-01-12
REGISTERED LAND SURVEYOR
REGISTRATION NO. 189377
STATE OF UTAH

TRI STATE LAND SURVEYING & CONSULTING


180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501


DATE SURVEYED: 02-15-12	SURVEYED BY: C.S.	VERSION: V2
DATE DRAWN: 10-01-12	DRAWN BY: V.H.	
REVISED:	SCALE: 1" = 1000'	

NAD 83 (SURFACE LOCATION)	NAD 83 (BOTTOM HOLE LOCATION)
LATITUDE = 40°05'53.21"	LATITUDE = 40°06'00.50"
LONGITUDE = 109°56'34.72"	LONGITUDE = 109°56'25.12"
NAD 27 (SURFACE LOCATION)	NAD 27 (BOTTOM HOLE LOCATION)
LATITUDE = 40°05'53.35"	LATITUDE = 40°06'00.63"
LONGITUDE = 109°56'32.19"	LONGITUDE = 109°56'22.59"

= SECTION CORNERS LOCATED

BASIS OF ELEV: Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'









Exhibit "B" Map

13-19-8-18 (Existing Well)
 Q-19-8-18 (Proposed Well)
 A-25-8-17 (Proposed Well)

**Legend**

- 1 Mile Radius
 ● Pad Location

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.



**Tri State
 Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
 F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

13-19-8-18 (Existing Well)
 Q-19-8-18 (Proposed Well)
 A-25-8-17 (Proposed Well)
 SEC. 19, T8S, R18E, S.L.B.&M. Uintah County, UT.

DRAWN BY:	A.P.C.	REVISED:	VERSION:
DATE:	10-01-2012		V2
SCALE:	1" = 2,000'		

TOPOGRAPHIC MAP

SHEET

D

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 10/31/2012

API NO. ASSIGNED: 43047532940000

WELL NAME: GMBU Q-19-8-18

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 646-4825

CONTACT: Mandie Crozier

PROPOSED LOCATION: SWSW 19 080S 180E

Permit Tech Review: ☒

SURFACE: 0690 FSL 0690 FWL

Engineering Review: ☐

BOTTOM: 1427 FSL 1435 FWL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 40.09816

LONGITUDE: -109.94305

UTM SURF EASTINGS: 590093.00

NORTHINGS: 4439188.00

FIELD NAME: EIGHT MILE FLAT

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-36846

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 1 - Federal

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: FEDERAL - WYB000493☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 437478☐ RDCC Review:☐ Fee Surface Agreement☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

☐ R649-2-3.

Unit: GMBU (GRRV)

☐ R649-3-2. General☐ R649-3-3. Exception☒ Drilling Unit

Board Cause No: Cause 213-11

Effective Date: 11/30/2009

Siting: Suspends General Siting

☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 4 - Federal Approval - dmason
15 - Directional - dmason
27 - Other - bhill

RECEIVED: November 21, 2012



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: GMBU Q-19-8-18
API Well Number: 43047532940000
Lease Number: UTU-36846
Surface Owner: FEDERAL
Approval Date: 11/21/2012

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 213-11. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Production casing cement shall be brought up to or above the top of the unitized interval for the Greater Monument Butte Unit (Cause No. 213-11).

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

NOV 01 2012

APPLICATION FOR PERMIT TO DRILL OR REENTER

BLM

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. UTU36846
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator NEWFIELD EXPLORATION COMPANY Contact: MANDIE CROZIER Email: mcrozier@newfield.com		7. If Unit or CA Agreement, Name and No. UTU87538X
3a. Address ROUTE 3 BOX 3630 MYTON, UT 84052	3b. Phone No. (include area code) Ph: 435.646.3721 Ext: 4825 Fx: 435.646.3031	8. Lease Name and Well No. GMBU Q-19-8-18
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface Lot 6 690FSL 690FWL 40.055321 N Lat, 109.563472 W Lon At proposed prod. zone NESW 1427FSL 1435FWL 40.060050 N Lat, 109.562512 W Lon		9. API Well No. 43-047-53294
14. Distance in miles and direction from nearest town or post office* 14.9 MILES SOUTHEAST OF MYTON, UT		10. Field and Pool, or Exploratory MONUMENT BUTTE
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 1427'	16. No. of Acres in Lease 1178.69	11. Sec., T., R., M., or Blk. and Survey or Area Sec 19 T8S R18E Mer SLB
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 1145'	19. Proposed Depth 6498 MD 6400 TVD	12. County or Parish UINTAH
21. Elevations (Show whether DF, KB, RT, GL, etc.) 5031 GL	22. Approximate date work will start 03/31/2012	13. State UT
23. Estimated duration 7 DAYS		17. Spacing Unit dedicated to this well 20.00
20. BLM/BIA Bond No. on file WYB000493		

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) MANDIE CROZIER Ph: 435.646.3721 Ext: 4825	Date 11/01/2012
Title REGULATORY TECH.		
Approved by (Signature) 	Name (Printed/Typed) Jerry Kenczka	Date SEP 16 2013
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #157176 verified by the BLM Well Information System
For NEWFIELD EXPLORATION COMPANY, sent to the Vernal
Committed to AFMSS for processing by JOHNETTA MAGEE on 11/16/2012 (13JM0065AE)

RECEIVED

NOTICE OF APPROVAL

SEP 20 2013

UDOGM

** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED **




UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company:	NEWFIELD PRODUCTION COMPANY	Location:	LOT 6 SEC. 19 T8S R18E
Well No:	GMBU Q-19-8-18	Lease No:	UTU36846
API No:	43-047-53294	Agreement:	UTU87538X

OFFICE NUMBER: (435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to: blm_ut_vn_opreport@blm.gov
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

***SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)***

STANDARD STIPULATIONS

Minerals and Paleontology

- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.

Green River District Reclamation Guidelines

The Operator will comply with the requirements of the ***Green River District (GRD) Reclamation Guidelines*** formalized by Green River District Instructional Memo UTG000-2011-003 on March 28, 2011. Documentation of the compliance will be as follows:

- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) that designates the proposed site-specific monitoring and reference sites chosen for the location. A description of the proposed sites shall be included, as well as a map showing the locations of the proposed sites.
- The operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) 3 growing seasons after reclamation efforts have occurred evaluating the status of the reclaimed areas in order to determine whether the BLM standards set forth in the GRD Reclamation Guidelines have been met (30% or greater basal cover).
- Prior to beginning new surface disturbance, the operator shall submit a Sundry Notice (Form 3160-5) to the BLM Authorized Officer (AO) providing the results of the noxious weed inventory described in the GRD Reclamation Guidelines (2011). If weeds are found the report shall include 1) A GPS location recorded in North American Datum 1983; 2) species; 3) canopy cover or number of plants; 4) and size of infestation (estimate square feet or acres. Information shall be also documented in the reclamation report.

CONDITIONS OF APPROVAL

Wildlife

In accordance with the Record of Decision for the Castle Peak and Eightmile Flat Oil and Gas Expansion Project, Newfield Rocky Mountains Inc., the following COA's are required:

- WFM-1 On level or gently sloping ground (5 percent slope or less) Newfield will elevate surface pipelines (4 inches or greater in diameter) a minimum of 6 inches above the ground to allow passage of small animals beneath the pipe. This ground clearance will be achieved by placing the pipeline on blocks at intervals of 150 to 200 feet.

- WFM-4 Newfield will install noise reduction devices on all pump jacks to reduce intermittent noise to 45 dBA at 660 feet from the source.

COA's derived from mitigating measures in the EA:

If construction and drilling is anticipated during any of the following wildlife seasonal spatial restrictions, a BLM biologist or a qualified consulting firm biologist must conduct applicable surveys using an accepted protocol prior to any ground disturbing activities.

- There is a ferruginous hawk nest within ½ mile of the proposed project area. If construction or drilling is proposed from March 1-August 31, then a nesting survey will be conducted by a qualified biologist according to protocol. If the nest is found to be inactive, then permission to proceed may be granted by the BLM Authorized Officer. If the nest is determined to be active, then the timing restriction will remain in effect.
- The proposed project is within 0.25 mile of burrowing owl habitat. If construction or drilling is proposed from March 1-August 31, then a nesting survey will be conducted by a qualified biologist according to protocol. If no nests are located, then permission to proceed may be granted by the BLM Authorized Officer. If a nest is located, then the timing restriction will remain in effect.

For protection of T&E Fish if drawing water from the Green River

- For areas of fresh water collection, an infiltration gallery will be constructed in a Service approved location. An infiltration gallery is basically a pit or trench dug within the floodplain to a depth below the water table. Water is drawn from the pit rather than from the river directly. If this is not possible, limit pumping within the river to off-channel locations that do not connect to the river during high spring flows.
- If water cannot be drawn using the measures above and the pump head will be located in the river channel where larval fish are known to occur, the following measures apply:
 - Avoid pumping from low-flow or no-flow areas as these habitats tend to concentrate larval fish
 - Avoid pumping to the greatest extent possible, during that period of the year when larval fish may be present (see previous bullet); and
 - Avoid pumping, to the greatest extent possible, during the midnight hours (10:00 p.m. to 2:00 a.m.) as larval drift studies indicate that this is a period of greatest daily activity. Dusk is the preferred pumping time, as larval drift abundance is lowest during this time.
 - Screen all pump intakes with 3/32-inch mesh material.
- Report any fish impinged on the intake screen to the FWS office (801.975.3330) and the:
Utah Division of Wildlife Resources
Northeastern Region
152 East 100 North
Vernal, UT 84078
(435) 781-9453

Air Quality

1. All internal combustion equipment will be kept in good working order.

2. Water or other approved dust suppressants will be used at construction sites and along roads, as determined appropriate by the Authorized Officer. Dust suppressant such as magnesium chloride or fresh water may be used, as needed, during the drilling phase.
3. Open burning of garbage or refuse will not occur at well sites or other facilities.
4. Drill rigs will be equipped with Tier II or better diesel engines.
5. Low bleed pneumatics will be installed on separator dump valves and other controllers.
6. During completion, no venting will occur, and flaring will be limited as much as possible. Production equipment and gathering lines will be installed as soon as possible.
7. Telemetry will be installed to remotely monitor and control production.
8. When feasible, two or more rigs (including drilling and completion rigs) will not be run simultaneously within 200 meters of each other. If two or more rigs must be run simultaneously within 200 meters of each other, then effective public health buffer zones out to 200 meters (m) from the nearest emission source will be implemented. Examples of an effective public health protection buffer zone include the demarcation of a public access exclusion zone by signage at intervals of every 250 feet that is visible from a distance of 125 feet during daylight hours, and a physical buffer such as active surveillance to ensure the property is not accessible by the public during drilling operations. Alternatively, the proponent may demonstrate compliance with the 1-hour NO₂ National Ambient Air Quality Standards (NAAQS) with appropriate and accepted near-field modeling. As part of this demonstration, the proponent may propose alternative mitigation that could include but is not limited to natural gas-fired drill rigs, installation of NO_x controls, time/use restrictions, and/or drill rig spacing.
9. All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horse power must not emit more than 2 grams of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower-hour.
10. All new and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 grams of NO_x per horsepower-hour.
11. Green completions will be used for all well completion activities where technically feasible.
12. Employ enhanced VOC emission controls with 95% control efficiency on production equipment having a potential to emit greater than 5 tons per year.

Threatened and Endangered Plants

Reinitiation of Section 7 consultation with the USFWS will be sought immediately if any loss of plants or occupied habitat for Pariette cactus or Uinta Basin hookless cactus is anticipated as a result of project activities.

**DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DOWNHOLE COAs:

Newfield Production Co. shall adhere to all referenced requirements in the SOP (version: "Greater Monument Butte Green River Development Program", Feb 16, 2012). The operator shall also comply with applicable laws and regulations; with lease terms Onshore Oil and Gas Orders, NTL's; and with other orders and instructions of the, authorized officer.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.

- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in CD (compact disc) format to the Vernal BLM Field Office. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).

- The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.
- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.

- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-36846
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: GMBU Q-19-8-18
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0690 FSL 0690 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 19 Township: 08.0S Range: 18.0E Meridian: S		9. API NUMBER: 43047532940000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: EIGHT MILE FLAT
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 11/1/2013	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 On 11/1/13 Set 9' of 14" conductor Drill 322' of 12 1/4" hole Set 8 jts of 8 5/8" surface casing set depth 335' KB. Cement surface casing with 200 sks G neat cement return 10 bbls to pit.

Accepted by the
 Utah Division of
 Oil, Gas and Mining
FOR RECORD ONLY
 November 05, 2013

NAME (PLEASE PRINT) Cherei Neilson	PHONE NUMBER 435 646-4883	TITLE Drilling Technician
SIGNATURE N/A	DATE 11/5/2013	

NEWFIELD**Casing****Conductor**

Legal Well Name GMBU Q-19-8-18				Wellbore Name Original Hole					
API/UWI 43047532940000		Surface Legal Location NESW Lot 6 690 FSL 690 FWL Sec 19 T8S R18E Mer SLB		Field Name GMBU CTB7		Well Type Development		Well Configuration Type Slant	
Well RC 500348139		County Uintah		State/Province Utah		Spud Date 11/1/2013 06:00		Final Rig Release Date	

Wellbore						
Wellbore Name Original Hole				Kick Off Depth (ftKB)		
Section Des		Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date	End Date
Conductor		14	10	19	11/1/2013	11/1/2013

Wellhead			
Type	Install Date	Service	Comment

Wellhead Components				
Des	Make	Model	SN	WP Top (psi)

Casing							
Casing Description Conductor		Set Depth (ftKB) 19		Run Date 11/1/2013		Set Tension (kips)	
Centralizers				Scratchers			

Casing Components												
Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft•lb)	Class	Max OD (in)
Conductor	14	13.500	36.75	H-40		1	9.00	10.0	19.0			

Jewelry Details										
External Casing Packer										
Type	Setting Requirement			Release Requirements			Inflation Method		Vol Inflation (gal)	Equiv Hole Sz (in)
Inflation Fluid Type	Infl Fl Dens (lb/gal)	P AV Set (psi)	AV Acting Pressure (psi)	P ICV Set (psi)	P ICV Act (psi)	ECP Load (1000lbf)		Seal Load (1000lbf)		

Slotted Liner							
% Open Area (%)	Perforation Min Dimension (in)	Perforation Max Dimension (in)	Axial Perf Spacing (ft)	Perf Rows	Blank Top Length (ft)	Blank Bottom Length (ft)	
Slot Description	Slot Pattern			Slot Length (in)	Slot Width (in)	Slot Frequency	Screen Gauge (ga)

Liner Hanger					
Retrievable?	Elastomer Type	Element Center Depth (ft)		Polish Bore Size (in)	Polish Bore Length (ft)
Slip Description				Set Mechanics	

Setting Procedure					
Unsetting Procedure					

NEWFIELD**Casing****Surface**

Legal Well Name GMBU Q-19-8-18				Wellbore Name Original Hole					
API/UWI 43047532940000		Surface Legal Location NESW Lot 6 690 FSL 690 FWL Sec 19 T8S R18E Mer SLB		Field Name GMBU CTB7		Well Type Development		Well Configuration Type Slant	
Well RC 500348139		County Uintah		State/Province Utah		Spud Date 11/1/2013 06:00		Final Rig Release Date	

Wellbore					
Wellbore Name Original Hole				Kick Off Depth (ftKB)	
Section Des	Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date	End Date
Conductor	14	10	19	11/1/2013	11/1/2013
Vertical	12 1/4	19	341	11/1/2013	11/1/2013

Wellhead				
Type	Install Date	Service	Comment	

Wellhead Components				
Des	Make	Model	SN	WP Top (psi)

Casing				
Casing Description Surface	Set Depth (ftKB)	Run Date	Set Tension (kips)	
	335	11/1/2013		
Centralizers	Scratchers			

Casing Components												
Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft•lb)	Class	Max OD (in)
Wellhead	8 5/8	8.097	24.00	J-55	ST&C	1	2.20	10.0	12.2			
Cutoff	8 5/8	8.097	24.00	J-55	ST&C	1	37.78	12.2	50.0			
Casing Joints	8 5/8	8.097	24.00	J-55	ST&C	6	239.69	50.0	289.7			
Float Collar	8 5/8	8.097	24.00	J-55	ST&C	1	0.93	289.7	290.6			
Shoe Joint	8 5/8	8.097	24.00	J-55	ST&C	1	43.07	290.6	333.7			
Guide Shoe	8 5/8	8.097	24.00	J-55	ST&C	1	1.40	333.7	335.1			

Jewelry Details									
External Casing Packer									
Type	Setting Requirement	Release Requirements			Inflation Method	Vol Inflation (gal)	Equiv Hole Sz (in)		
Inflation Fluid Type	Infl FI Dens (lb/gal)	P AV Set (psi)	AV Acting Pressure (psi)	P ICV Set (psi)	P ICV Act (psi)	ECP Load (1000lbf)	Seal Load (1000lbf)		

Slotted Liner							
% Open Area (%)	Perforation Min Dimension (in)	Perforation Max Dimension (in)	Axial Perf Spacing (ft)	Perf Rows	Blank Top Length (ft)	Blank Bottom Length (ft)	
Slot Description	Slot Pattern			Slot Length (in)	Slot Width (in)	Slot Frequency	Screen Gauge (ga)

Liner Hanger				
Retrievable?	Elastomer Type	Element Center Depth (ft)	Polish Bore Size (in)	Polish Bore Length (ft)
Slip Description			Set Mechanics	

Setting Procedure				
Unsetting Procedure				

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# ProPetro 10
Submitted By Branden Arnold Phone Number 435-401-0223
Well Name/Number GMBU Q-19-8-18
Qtr/Qtr SE/NW Section 19 Township 8S Range 18E
Lease Serial Number UTU-36846
API Number 43-047-53294

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 10/31/13 10:00 AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 10/31/13 6:00 AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

RECEIVED

OCT 30 2013

DIV. OF OIL, GAS & MINING

Date/Time _____ AM ☐ PM ☐

Remarks _____

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# NDSI SS # 2

Submitted By Justin Crum Phone Number 823-6732

Well Name/Number GMBU Q-19-8-18

Qtr/Qtr Lot 6 Section 19 Township 8S Range 18E

Lease Serial Number UTU- 36846

API Number 43-047-53294

TD Notice – TD is the final drilling depth of hole.

Date/Time 11/23/2013 2:00 AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 11/24/2013 2:00 AM ☐ PM ☐

RECEIVED

NOV 22 2013

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-36846
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: GMBU Q-19-8-18
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0690 FSL 0690 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSW Section: 19 Township: 08.0S Range: 18.0E Meridian: S		9. API NUMBER: 43047532940000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: EIGHT MILE FLAT
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/30/2013	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between; align-items: flex-start;"> <div style="width: 60%;"> <p>The above well was placed on production on 12/30/2013 at 16:00 hours.</p> </div> <div style="width: 35%; text-align: center;"> <p>Accepted by the Utah Division of Oil, Gas and Mining</p> <p>FOR RECORD ONLY</p> <p>January 03, 2014</p> </div> </div>		
NAME (PLEASE PRINT) Jennifer Peatross	PHONE NUMBER 435 646-4885	TITLE Production Technician
SIGNATURE N/A	DATE 1/2/2014	

Form 3160-4
(March 2012)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0137
Expires: October 31, 2014

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well ☒ Oil Well ☐ Gas Well ☐ Dry ☐ Other
b. Type of Completion: ☒ New Well ☐ Work Over ☐ Deepen ☐ Plug Back ☐ Diff. Resrv.,
Other: _____2. Name of Operator
NEWFIELD PRODUCTION COMPANY3. Address ROUTE #3 BOX 3630
MYTON, UT 840523a. Phone No. (include area code)
Ph:435-646-3721

4. Location of Well (Report location clearly and in accordance with Federal requirements)*

At surface 690' FSL 690' FWL (LOT#6, SW/SW) SEC 19 T8S R18E (UTU-36846)

At top prod. interval reported below 1234' FSL 1219' FWL (LOT#6, SW/SW) SEC 19 T8S R18E (UTU-36846)

At total depth 1450' FSL 1447' FWL (NE/SW) SEC 19 T8S R18E (UTU-36846)

14. Date Spudded
11/01/201315. Date T.D. Reached
11/24/201316. Date Completed 12/23/2013
☐ D & A ☒ Ready to Prod.5. Lease Serial No.
UTU36846

6. If Indian, Allottee or Tribe Name

7. Unit or CA Agreement Name and No.
UTU87538X8. Lease Name and Well No.
GMBU Q-19-8-189. API Well No.
43-047-5329410. Field and Pool or Exploratory
MONUMENT BUTTE11. Sec., T., R., M., on Block and
Survey or Area SEC 19 T8S R18E Mer SLB

12. County or Parish

13. State

UINTAH

UT

17. Elevations (DF, RKB, RT, GL)*
5031' GL 5041' KB18. Total Depth: MD 6675'
TVD 6573'19. Plug Back T.D.: MD 6640'
TVD20. Depth Bridge Plug Set: MD
TVD21. Type Electric & Other Mechanical Logs Run (Submit copy of each)
DUAL IND GRD, SP, COMP. NEUTRON, GR, CALIPER, CMT BOND22. Was well cored? ☒ No ☐ Yes (Submit analysis)
Was DST run? ☒ No ☐ Yes (Submit report)
Directional Survey? ☐ No ☒ Yes (Submit copy)

23. Casing and Liner Record (Report all strings set in well)

Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cement Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
12-1/4"	8-5/8" J-55	24	0'	335'		200CLASS G			
7-7/8"	5-1/2" J-55	15.50	0'	6665'		290 Econocem		65'	
						420Expandacem			

24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2-7/8"	EOT@6281'	TA@6142'						

25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) Green River	4845'	6200'	4845' - 6200' MD	0.34	59	
B)						
C)						
D)						

27. Acid, Fracture, Treatment, Cement Squeeze, etc.

Depth Interval	Amount and Type of Material
4845' - 6200' MD	Frac w/ 349926#s of 20/40 white sand in 3590 bbls of Lightning 17 fluid, in 4 stages.

28. Production - Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
12/30/13	1/9/14	24	→	136	72	60			2.5 X 1.75 X 24' RHAC
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→					PRODUCING	

28a. Production - Interval B

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers
GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MARK GARDEN GULCH 1	4240' 4423'
				GARDEN GULCH 2 POINT 3	4548' 4824'
				X MRKR Y MRKR	5048' 5083'
				DOUGLAS CREEK MRK BI CARBONATE MRK	5219' 5496'
				B LIMESTONE MRK CASTLE PEAK	5598' 6079'
				BASAL CARBONATE WASATCH	6489' 6612'

32. Additional remarks (include plugging procedure):

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Drilling daily activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Heather CalderTitle Regulatory TechnicianSignature Heather CalderDate 01/14/2014

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)

RECEIVED: Jan. 22, 2014



NEWFIELD EXPLORATION

USGS Myton SW (UT)
SECTION 19 T8S R18E
Q-19-8-18
Wellbore #1

Design: Actual

End of Well Report

25 November, 2013





Payzone Directional

End of Well Report

API Well Number: 43047532940000



Company: NEWFIELD EXPLORATION	Local Co-ordinate Reference: Well Q-19-8-18
Project: USGS Myton SW (UT)	TVD Reference: Q-19-8-18 @ 5041.0usft
Site: SECTION 19 T8S R18E	MD Reference: Q-19-8-18 @ 5041.0usft
Well: Q-19-8-18	North Reference: True
Wellbore: Wellbore #1	Survey Calculation Method: Minimum Curvature
Design: Actual	Database: EDM 5000.1 Single User Db

Project USGS Myton SW (UT), DUCHESNE COUNTY, UT, USA	System Datum: Mean Sea Level
--	--

Site SECTION 19 T8S R18E, SEC 19 T8S R18E	Northings: 7,209,998.99 usft	Latitude: 40° 6' 10.109 N
Site Position: From: Lat/Long	Easting: 2,078,000.00 usft	Longitude: 109° 56' 7.952 W
Position Uncertainty: 0.0 usft	Slot Radius: 13-3/16 "	Grid Convergence: 1.00 °

Well Q-19-8-18, SHL LAT: 40 05 53.21 LONG: -109 56 34.72	Northings: 7,208,253.06 usft	Latitude: 40° 5' 53.210 N
Well Position +N/-S +E/-W	Easting: 2,075,950.24 usft	Longitude: 109° 56' 34.720 W
Position Uncertainty 0.0 usft	Wellhead Elevation: 5,041.0 usft	Ground Level: 5,031.0 usft

Wellbore Wellbore #1		
--------------------------------	--	--

Magnetics IGRF2010	Sample Date 9/24/2012	Declination (°) 11.11	Dip Angle (°) 65.83	Field Strength (nT) 52,194
------------------------------	---------------------------------	------------------------------------	----------------------------------	---

Design Actual				
-------------------------	--	--	--	--

Audit Notes: Version: 1.0	Phase: ACTUAL	Tie On Depth: 0.0		
-------------------------------------	-------------------------	-----------------------------	--	--

Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)
	0.0	0.0	0.0	44.88

Survey Program From (usft)	Date 11/25/2013	To (usft)	Survey (Wellbore)	Tool Name	Description
345.0		6,675.0	Survey #1 (Wellbore #1)	MWD	MWD - Standard

RECEIVED: Jan. 22, 2014



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 19 T8S R18E
Well: Q-19-8-18
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well Q-19-8-18
TVD Reference: Q-19-8-18 @ 5041.0usft
MD Reference: Q-19-8-18 @ 5041.0usft
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
	345.0	0.04	194.41	345.0	-0.1	-0.1	0.0	0.01	0.01	0.00
	375.0	0.04	237.96	375.0	-0.1	-0.1	0.0	0.10	0.00	145.17
	405.0	0.26	287.75	405.0	-0.2	-0.1	-0.1	0.79	0.73	165.97
	436.0	0.18	255.93	436.0	-0.2	-0.1	-0.2	0.46	-0.26	-102.65
	466.0	0.22	304.14	466.0	-0.3	-0.1	-0.3	0.56	0.13	160.70
	496.0	0.41	317.33	496.0	-0.3	0.0	-0.4	0.67	0.63	43.97
	527.0	0.20	271.10	527.0	-0.3	0.1	-0.6	0.99	-0.68	-149.13
	558.0	0.40	52.40	558.0	-0.3	0.2	-0.5	1.84	0.65	455.81
	588.0	0.80	65.60	588.0	0.0	0.3	-0.3	1.40	1.33	44.00
	619.0	1.00	55.10	619.0	0.5	0.6	0.2	0.83	0.65	-33.87
	649.0	1.40	49.80	649.0	1.1	1.0	0.6	1.38	1.33	-17.67
	680.0	1.90	44.90	680.0	2.0	1.6	1.3	1.67	1.61	-15.81
	711.0	2.60	42.90	710.9	3.2	2.4	2.1	2.27	2.26	-6.45
	741.0	3.00	46.00	740.9	4.7	3.5	3.2	1.43	1.33	10.33
	771.0	3.30	46.10	770.9	6.4	4.6	4.4	1.00	1.00	0.33
	802.0	3.60	44.60	801.8	8.2	5.9	5.7	1.01	0.97	-4.84
	832.0	4.00	44.20	831.7	10.2	7.4	7.1	1.34	1.33	-1.33
	862.0	4.60	42.60	861.7	12.5	9.0	8.6	2.04	2.00	-5.33
	892.0	5.20	43.40	891.6	15.0	10.9	10.4	2.01	2.00	2.67
	923.0	5.90	44.90	922.4	18.0	13.0	12.5	2.31	2.26	4.84
	953.0	6.30	45.70	952.2	21.2	15.3	14.7	1.36	1.33	2.67
	983.0	6.50	42.40	982.0	24.5	17.7	17.0	1.40	0.67	-11.00
	1,014.0	6.80	44.90	1,012.8	28.1	20.3	19.5	1.34	0.97	8.06
	1,057.0	7.00	47.00	1,055.5	33.3	23.9	23.2	0.75	0.47	4.88
	1,101.0	7.90	47.10	1,099.2	39.0	27.7	27.4	2.05	2.05	0.23
	1,145.0	8.40	46.40	1,142.7	45.2	32.0	32.0	1.16	1.14	-1.59

RECEIVED: Jan. 22, 2014



Payzone Directional
End of Well Report

API Well Number: 43047532940000



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 19 T8S R18E
Well: Q-19-8-18
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference:
TVD Reference:
MD Reference:
North Reference:
Survey Calculation Method:
Database:

Well Q-19-8-18
Q-19-8-18 @ 5041.0usft
Q-19-8-18 @ 5041.0usft
True
Minimum Curvature
EDM 5000.1 Single User Db

Survey

MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Buld (°/100usft)	Turn (°/100usft)
1,189.0	9.10	46.40	1,186.2	51.9	36.6	36.8	1.59	1.59	0.00
1,233.0	9.90	45.30	1,229.6	59.2	41.7	42.0	1.86	1.82	-2.50
1,277.0	10.63	45.26	1,272.9	67.0	47.2	47.6	1.66	1.66	-0.09
1,320.0	11.00	46.40	1,315.1	75.1	52.8	53.4	0.99	0.86	2.65
1,364.0	11.30	45.10	1,358.3	83.6	58.8	59.5	0.89	0.68	-2.95
1,408.0	11.65	45.52	1,401.4	92.4	64.9	65.7	0.82	0.80	0.95
1,452.0	11.95	44.07	1,444.5	101.3	71.3	72.0	0.96	0.68	-3.30
1,496.0	11.87	44.20	1,487.5	110.4	77.8	78.3	0.19	-0.18	0.30
1,540.0	12.00	43.06	1,530.6	119.5	84.4	84.6	0.61	0.30	-2.59
1,583.0	12.13	42.31	1,572.6	128.5	91.0	90.7	0.47	0.30	-1.74
1,627.0	12.22	42.00	1,615.7	137.8	97.9	96.9	0.25	0.20	-0.70
1,671.0	12.08	41.52	1,658.7	147.0	104.8	103.1	0.39	-0.32	-1.09
1,715.0	12.04	40.60	1,701.7	156.2	111.7	109.2	0.45	-0.09	-2.09
1,759.0	11.80	41.00	1,744.7	165.3	118.6	115.1	0.58	-0.55	0.91
1,802.0	12.00	40.90	1,786.8	174.1	125.3	120.9	0.47	0.47	-0.23
1,846.0	12.00	41.90	1,829.9	183.2	132.2	127.0	0.47	0.00	2.27
1,890.0	11.70	43.40	1,872.9	192.3	138.8	133.1	0.98	-0.68	3.41
1,934.0	11.63	43.60	1,916.0	201.2	145.3	139.2	0.18	-0.16	0.45
1,978.0	12.00	42.50	1,959.1	210.2	151.9	145.3	0.98	0.84	-2.50
2,021.0	11.65	43.60	2,001.2	219.0	158.3	151.4	0.97	-0.81	2.56
2,065.0	11.30	43.90	2,044.3	227.7	164.6	157.4	0.81	-0.80	0.68
2,109.0	10.80	43.80	2,087.5	236.2	170.7	163.3	1.14	-1.14	-0.23
2,153.0	10.80	43.80	2,130.7	244.4	176.7	169.0	0.00	0.00	0.00
2,197.0	11.30	40.20	2,173.9	252.8	182.9	174.6	1.94	1.14	-8.18
2,240.0	12.40	37.60	2,216.0	261.6	189.8	180.1	2.84	2.56	-6.05
2,284.0	12.90	36.60	2,258.9	271.1	197.5	185.9	1.24	1.14	-2.27
2,328.0	13.40	34.20	2,301.7	281.0	205.6	191.7	1.68	1.14	-5.45

RECEIVED: Jan. 22, 2014



Payzone Directional
End of Well Report



API Well Number: 43047532940000

Company: NEWFIELD EXPLORATION
Project: USGS Mylon SW (UT)
Site: SECTION 19 T8S R18E
Well: Q-19-8-18
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well Q-19-8-18
TVD Reference: Q-19-8-18 @ 5041.0usft
MD Reference: Q-19-8-18 @ 5041.0usft
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	EW (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	2,372.0	13.00	32.50	2,344.6	290.9	214.0	197.3	1.27	-0.91	-3.86
	2,415.0	11.50	30.00	2,386.6	299.7	221.8	202.0	3.70	-3.49	-5.81
	2,459.0	10.90	30.60	2,429.8	308.0	229.2	206.3	1.39	-1.36	1.36
	2,503.0	10.50	32.70	2,473.0	315.9	236.2	210.6	1.27	-0.91	4.77
	2,546.0	10.24	35.90	2,515.3	323.5	242.6	215.0	1.47	-0.60	7.44
	2,590.0	9.80	40.30	2,558.6	331.1	248.6	219.7	2.01	-1.00	10.00
	2,634.0	9.70	43.00	2,602.0	338.6	254.1	224.6	1.06	-0.23	6.14
	2,678.0	9.90	46.00	2,645.3	346.1	259.5	229.9	1.25	0.45	6.82
	2,722.0	9.60	48.90	2,688.7	353.5	264.5	235.4	1.31	-0.68	6.59
	2,765.0	9.40	50.10	2,731.1	360.6	269.1	240.8	0.65	-0.47	2.79
	2,809.0	8.90	47.90	2,774.6	367.6	273.7	246.0	1.39	-1.14	-5.00
	2,853.0	8.50	46.80	2,818.1	374.2	278.2	250.9	0.98	-0.91	-2.50
	2,897.0	8.50	47.60	2,861.6	380.7	282.6	255.7	0.27	0.00	1.82
	2,941.0	8.60	49.30	2,905.1	387.2	287.0	260.6	0.62	0.23	3.86
	2,984.0	9.40	50.00	2,947.6	393.9	291.3	265.7	1.88	1.86	1.63
	3,028.0	10.70	53.50	2,990.9	401.6	296.1	271.8	3.26	2.95	7.95
	3,072.0	11.20	55.50	3,034.1	409.8	300.9	278.6	1.43	1.14	4.55
	3,116.0	11.60	53.60	3,077.2	418.4	306.0	285.6	1.25	0.91	-4.32
	3,160.0	11.70	53.00	3,120.3	427.2	311.3	292.8	0.36	0.23	-1.36
	3,203.0	11.30	51.10	3,162.4	435.7	316.6	299.5	1.28	-0.93	-4.42
	3,247.0	10.40	47.20	3,205.7	443.9	322.0	305.8	2.64	-2.05	-8.86
	3,291.0	9.60	44.70	3,249.0	451.6	327.3	311.3	2.07	-1.82	-5.68
	3,335.0	8.70	46.70	3,292.4	458.5	332.2	316.3	2.17	-2.05	4.55
	3,379.0	8.40	47.00	3,335.9	465.1	336.6	321.1	0.69	-0.68	0.68
	3,423.0	8.00	49.10	3,379.5	471.3	340.8	325.7	1.14	-0.91	4.77
	3,466.0	8.90	50.30	3,422.0	477.6	344.9	330.6	2.13	2.09	2.79
	3,510.0	9.90	50.60	3,465.4	484.8	349.5	336.1	2.28	2.27	0.68

RECEIVED: Jan. 22, 2014



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 19 T8S R18E
Well: Q-19-8-18
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well Q-19-8-18
TVD Reference: Q-19-8-18 @ 5041.0usft
MD Reference: Q-19-8-18 @ 5041.0usft
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	D Leg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	3,554.0	10.70	50.40	3,508.7	492.6	354.5	342.2	1.82	1.82	-0.45
	3,598.0	10.80	47.40	3,551.9	500.8	359.9	348.3	1.29	0.23	-6.82
	3,642.0	10.80	43.80	3,595.2	509.1	365.6	354.2	1.53	0.00	-8.18
	3,686.0	11.20	43.20	3,638.4	517.4	371.7	360.0	0.95	0.91	-1.36
	3,729.0	12.00	43.20	3,680.5	526.1	378.0	365.9	1.86	1.86	0.00
	3,773.0	12.30	43.50	3,723.5	535.3	384.8	372.3	0.70	0.68	0.68
	3,817.0	12.30	43.10	3,766.5	544.7	391.6	378.7	0.19	0.00	-0.91
	3,861.0	11.73	43.15	3,809.5	553.9	398.3	385.0	1.30	-1.30	0.11
	3,904.0	11.40	42.60	3,851.6	562.5	404.6	390.8	0.81	-0.77	-1.28
	3,948.0	11.20	44.50	3,894.8	571.1	410.8	396.8	0.96	-0.45	4.32
	3,992.0	11.30	46.00	3,937.9	579.7	416.9	402.9	0.70	0.23	3.41
	4,036.0	11.60	47.60	3,981.1	588.4	422.9	409.2	0.99	0.68	3.64
	4,080.0	12.30	48.20	4,024.1	597.5	429.0	416.0	1.62	1.59	1.36
	4,124.0	13.00	48.20	4,067.0	607.1	435.4	423.2	1.59	1.59	0.00
	4,167.0	12.70	46.30	4,109.0	616.7	441.9	430.2	1.21	-0.70	-4.42
	4,211.0	11.90	44.80	4,152.0	626.1	448.4	436.9	1.96	-1.82	-3.41
	4,255.0	11.30	43.50	4,195.1	634.9	454.8	443.1	1.49	-1.36	-2.95
	4,299.0	11.10	43.90	4,238.2	643.4	461.0	449.0	0.49	-0.45	0.91
	4,343.0	11.30	46.10	4,281.4	652.0	467.0	455.0	1.07	0.45	5.00
	4,387.0	10.90	47.10	4,324.6	660.5	472.8	461.2	1.01	-0.91	2.27
	4,430.0	11.10	45.10	4,366.8	668.7	478.5	467.1	1.00	0.47	-4.65
	4,474.0	11.80	42.60	4,409.9	677.4	484.8	473.1	1.95	1.59	-5.68
	4,518.0	12.30	43.30	4,452.9	686.6	491.5	479.4	1.18	1.14	1.59
	4,562.0	12.20	44.20	4,495.9	695.9	498.3	485.8	0.49	-0.23	2.05
	4,606.0	12.00	43.80	4,538.9	705.1	504.9	492.3	0.49	-0.45	-0.91
	4,649.0	12.20	44.10	4,581.0	714.1	511.4	498.5	0.49	0.47	0.70
	4,693.0	12.30	43.70	4,624.0	723.5	518.1	505.0	0.30	0.23	-0.91

RECEIVED: Jan. 22, 2014



Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 19 T8S R18E
Well: Q-19-8-18
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference: Well Q-19-8-18
TVD Reference: Q-19-8-18 @ 5041.0usft
MD Reference: Q-19-8-18 @ 5041.0usft
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Bulid (°/100usft)	Turn (°/100usft)
	4,737.0	11.80	43.60	4,667.0	732.7	524.8	511.3	1.14	-1.14	-0.23
	4,781.0	11.60	43.80	4,710.1	741.6	531.2	517.5	0.46	-0.45	0.45
	4,825.0	11.10	44.10	4,753.2	750.2	537.5	523.5	1.14	-1.14	0.68
	4,869.0	11.00	44.00	4,796.4	758.7	543.5	529.4	0.23	-0.23	-0.23
	4,912.0	10.50	45.30	4,838.7	766.7	549.2	535.0	1.29	-1.16	3.02
	4,956.0	9.70	45.70	4,882.0	774.4	554.6	540.5	1.83	-1.82	0.91
	5,000.0	9.80	46.10	4,925.4	781.9	559.8	545.8	0.27	0.23	0.91
	5,044.0	9.60	46.00	4,968.7	789.3	565.0	551.2	0.46	-0.45	-0.23
	5,088.0	9.20	47.00	5,012.1	796.4	569.9	556.4	0.98	-0.91	2.27
	5,131.0	9.70	47.80	5,054.6	803.5	574.7	561.6	1.20	1.16	1.86
	5,175.0	9.90	47.20	5,097.9	811.0	579.8	567.1	0.51	0.45	-1.36
	5,219.0	9.90	43.90	5,141.3	818.5	585.1	572.5	1.29	0.00	-7.50
	5,263.0	10.00	44.10	5,184.6	826.1	590.5	577.8	0.24	0.23	0.45
	5,307.0	10.30	44.20	5,227.9	833.9	596.1	583.2	0.68	0.68	0.23
	5,350.0	10.90	44.40	5,270.2	841.8	601.8	588.7	1.40	1.40	0.47
	5,394.0	10.90	45.20	5,313.4	850.1	607.7	594.6	0.34	0.00	1.82
	5,438.0	11.00	42.90	5,356.6	858.5	613.7	600.4	1.02	0.23	-5.23
	5,482.0	12.20	41.90	5,399.7	867.3	620.2	606.4	2.77	2.73	-2.27
	5,526.0	12.20	42.10	5,442.7	876.6	627.1	612.6	0.10	0.00	0.45
	5,569.0	11.90	40.50	5,484.7	885.6	633.9	618.5	1.04	-0.70	-3.72
	5,613.0	11.80	44.20	5,527.8	894.6	640.5	624.6	1.74	-0.23	8.41
	5,657.0	12.30	46.10	5,570.8	903.8	647.0	631.1	1.45	1.14	4.32
	5,701.0	12.30	46.00	5,613.8	913.1	653.5	637.8	0.05	0.00	-0.23
	5,745.0	13.00	45.60	5,656.8	922.8	660.2	644.8	1.60	1.59	-0.91
	5,788.0	12.80	45.60	5,698.7	932.4	666.9	651.6	0.47	-0.47	0.00
	5,832.0	12.52	45.43	5,741.6	942.0	673.7	658.5	0.64	-0.64	-0.39
	5,876.0	12.80	45.80	5,784.5	951.7	680.4	665.4	0.66	0.64	0.84

Company: NEWFIELD EXPLORATION
Project: USGS Myton SW (UT)
Site: SECTION 19 T8S R18E
Well: Q-19-8-18
Wellbore: Wellbore #1
Design: Actual

Local Co-ordinate Reference:
TVD Reference: Well Q-19-8-18
MD Reference: Q-19-8-18 @ 5041.0usft
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey	MD (usft)	Inc (°)	Azi (azimuth) (°)	TVD (usft)	V. Sec (usft)	N/S (usft)	E/W (usft)	DLeg (°/100usft)	Build (°/100usft)	Turn (°/100usft)
	5,920.0	12.90	46.80	5,827.4	961.4	687.2	672.5	0.55	0.23	2.27
	5,964.0	13.10	46.50	5,870.3	971.3	694.0	679.7	0.48	0.45	-0.68
	6,007.0	13.50	47.00	5,912.1	981.2	700.8	686.9	0.97	0.93	1.16
	6,051.0	13.00	46.60	5,955.0	991.3	707.7	694.2	1.16	-1.14	-0.91
	6,095.0	11.30	47.20	5,998.0	1,000.6	714.0	701.0	3.87	-3.86	1.36
	6,139.0	10.70	46.60	6,041.2	1,009.0	719.7	707.1	1.39	-1.36	-1.36
	6,183.0	10.10	47.50	6,084.5	1,016.9	725.2	712.9	1.41	-1.36	2.05
	6,227.0	9.50	49.30	6,127.8	1,024.4	730.1	718.5	1.53	-1.36	4.09
	6,270.0	9.00	49.60	6,170.3	1,031.3	734.6	723.8	1.17	-1.16	0.70
	6,314.0	8.50	50.10	6,213.7	1,037.9	738.9	728.9	1.15	-1.14	1.14
	6,358.0	7.70	51.00	6,257.3	1,044.1	742.9	733.7	1.84	-1.82	2.05
	6,402.0	6.80	53.10	6,301.0	1,049.6	746.3	738.0	2.13	-2.05	4.77
	6,446.0	6.15	52.42	6,344.7	1,054.5	749.3	742.0	1.49	-1.48	-1.55
	6,489.0	5.58	52.77	6,387.4	1,058.9	752.0	745.5	1.33	-1.33	0.81
	6,533.0	4.66	54.62	6,431.3	1,062.7	754.3	748.6	2.12	-2.09	4.20
	6,577.0	4.22	55.19	6,475.1	1,066.1	756.3	751.4	1.01	-1.00	1.30
	6,623.0	3.78	55.76	6,521.0	1,069.3	758.1	754.1	0.96	-0.96	1.24
	6,675.0	3.78	56.00	6,572.9	1,072.6	760.0	756.9	0.03	0.00	0.46

Checked By: _____

Approved By: _____




Date: _____

RECEIVED: Jan. 22, 2014



Project: USGS Myton SW (UT)
Site: SECTION 19 T8S R18E
Well: Q-19-8-18
Wellbore: Wellbore #1
Design: Actual

Azimuths to True North
Magnetic North: 11.11°
Magnetic Field
Strength: 52193.6snT
Dip Angle: 65.83°
Date: 9/24/2012
Model: IGRF2010



Design: Actual (Q-19-8-18/Wellbore #1)

Created By: *Matthew Lindon*

Date:

7:34, November 25 20

THIS SURVEY IS CORRECT TO THE BEST OF
MY KNOWLEDGE AND IS SUPPORTED
BY ACTUAL FIELD DATA

NEWFIELD



Well Name: GMBU Q-19-8-18

Summary Rig Activity

Job Category		Job Start Date		Job End Date	
Daily Operations					
Report Start Date	Report End Date	24hr Activity Summary			
12/13/2013	12/14/2013	R/U Perforators W/L RIH Prefrom CBL F/ PBTD to sur. under 0#. R/U 4G testers P/T all components of Frac stack 250 low for 5-min. and 4300 high for 10-min. also test csg. to 4300 for 30-min.(all tests good) P/U RIH and Perf stg. 1 SWI			
Start Time	End Time	Comment			
07:00	09:30	R/U Perforators W/L RIH w/ CBL tools tag PBTD @ 6610' log OOH w/ 0# @ 75' pm, est. crnt top @ 65'			
Start Time	End Time	Comment			
09:30	11:30	R/U 4G testers, P/T csg. to 4300# hold for 30-min. (good) P/T all components of Frac stack @ flowback lines 250# low for 5- min. and 4300# high for 10-min. (all tests good)			
Start Time	End Time	Comment			
11:30	12:00	R/U w/ Perforators again P/U RIH w/ 3-1/8 perf gun perf stg. 1 CP-2 & CP-half snds f/ (6197-6200)(6098-6100) 3 spf @ 120 deg. POOH L/D guns & R/D W/L move over to A-25-8-17			
Start Time	End Time	Comment			
12:00	00:00				
Report Start Date	Report End Date	24hr Activity Summary			
12/16/2013	12/17/2013	Frac stgs. 1 & 2 sand screws engaged 70 bbls into flush on stg 2 leaving ~150' in wellbore SWI and let sand settle overnight before RIH w/ W/L			
Start Time	End Time	Comment			
00:00	06:00				
Start Time	End Time	Comment			
06:00	12:00	Move in R/U Nabors Frac Equip.			
Start Time	End Time	Comment			
12:00	13:00	STG. 1 Pres. test frac iron to 5300# open well w/ 80# break perfs @ 3801, w/ 2.4 bbls @ 3.5 bpm, F/ inj rate 4.2 bpm @ 2321 and 6.6 tll bbls, ISIP @ 1410 for FG of .68, 1-min. 702.4-min.622, Frac stg. 1 w/ 35.778 20/40, 17# delta fluid, Max pres. 3874, Avg. pres. 2368, Max Rt. 32.2, Avg. Rt. 24.2, ISDP @ 1202 and FG. of 65, 5-min. 1089, 10-min. 1038, 15-min. 994, Shut well in and turn over to Perforators W/L 500 bwtr			
Start Time	End Time	Comment			
13:00	15:00	R/U W/L Pres. test lub to 4000# (good) RIH @ 320' pm set CFP @ 6070' and perf stg. # 2 LODC sands f/ (6023 -24')(6008-10')(5985-87') 3 spf @ 120 deg. Phasing POOH L/D setting tool and guns Turn over to Nabors			
Start Time	End Time	Comment			
15:00	16:00	STG. 2 Pres. test frac iron to 5300# open well w/ 527# break perfs @ 2209, w/ 8.9 bbls @ 7.2 bpm, Frac stg. 2 w/ 1117.858 of 160K cut sand @ end of 4-5# ramp Max pres.3500 , Avg. pres. 2831, Max Rt. 32.1, Avg. Rt. 31, ISDP @ 2972, and FG. of 1.0, 5-min.1806, 10-min.1682, 15-min. 1726, (NOTE: 70 BBLS INTO FLUSH SAND SCREWS ENGAGED AND TURNED 2000# OF SAND INTO WELL BORE ~150' LEFT SAND TO SETTLE OVERNIGHT BEFORE MAKING W/L RUN) SWIFN MOVE OVER TO THE A-25-8-17			
Start Time	End Time	Comment			
16:00	00:00				
Report Start Date	Report End Date	24hr Activity Summary			
12/17/2013	12/18/2013	RIH tag settled sand @ 5742' R/U Nabors to well perf stg. 3. Frac stg 3 Perf & Frac stg 4 Open well to flowback			
Start Time	End Time	Comment			
00:00	07:00				
Start Time	End Time	Comment			
07:00	09:30	SIP 2000# R/U Perforators W/L RIH w/ dummy tools and tag fill @ 5742' leaving 18' from btm perf on stg. 3 POOH and R/U Nabors frac equip.			
Start Time	End Time	Comment			
09:30	10:30	RIH w/ 3-1/8 perf guns and shoot stg. 3, A1 & C-sand f/ (5723-25')(5719-20')(5703-04')(5463-65')(5442-44') POOH and discovered last 2' gun did not fire			
Start Time	End Time	Comment			
10:30	12:30	Repair gun (Broke wire) P/U RIH and perf (5442-44') POOH turn over to Nabors			

NEWFIELD



Well Name: GMBU Q-19-8-18

Summary Rig Activity

Start Time	12:30	End Time	13:30	Comment
Start Time	13:30	End Time	14:30	Comment
Start Time	14:30	End Time	15:30	Comment
Start Time	15:30	End Time	19:30	Comment
Start Time	19:30	End Time	00:00	Comment
Report Start Date	12/18/2013	Report End Date	12/19/2013	24hr Activity Summary
Start Time	00:00	End Time	04:30	Comment
Start Time	04:30	End Time	06:30	Comment
Start Time	06:30	End Time	09:00	Comment
Start Time	09:00	End Time	10:00	Comment
Start Time	10:00	End Time	11:00	Comment
Start Time	11:00	End Time	13:30	Comment
Start Time	13:30	End Time	18:00	Comment
Start Time	18:00	End Time	19:00	Comment
Start Time	19:00	End Time	00:00	Comment
Report Start Date	12/19/2013	Report End Date	12/20/2013	24hr Activity Summary
Start Time	00:00	End Time	06:00	Comment
Start Time	06:00	End Time	07:00	Comment
Start Time	07:00	End Time	09:00	Comment
Start Time	09:00	End Time	11:30	Comment

STG. 3 Pres. test frac iron to 5300# open well w/ 586# break perfs @ 1481, w/ 2.4 bbls @ 2.4 bpm, Frac stg. 3 w/ 145,986 Max pres. 2704, Avg. pres. 2024, Max Rt. 43.8, Avg. Rt. 42.7, ISDP @ 1372, and FG. of 69, 5-min. 1333, 10-min. 1289, 15-min. 1230, Shut well in and turn over to Extreme W/L 1201 bwt

R/U W/L Pres. test lub to 4000# (good) RIH @ 320' pm set CFP @ 4930' and perf stg. # 3 PB-7 sands f/ (4856-59)(4845-47'') 3 spf @ 120 deg. Phasing POOH L/D setting tool and guns Turn over to Nabors

STG. 4 Pres. test frac iron to 5300# open well w/ 996# break perfs @ 1957, w/ 2.8 bbls @ 4.3 bpm, Frac stg. 4 w/ 50,304 Max pres. 3509, Avg. pres. 2970, Max Rt. 31.9, Avg. Rt. 30.1, ISDP @ 1823, and FG. of 83, 5-min. 1758, 10-min. 1670, 15-min. 1604, 1201 bwt

Open well @ 3 bpm recovered ~720 bbls started see traces of oil SWI

PT BOPE, prep & tally tbgs. P/U RIH w/ D/O BHA followed by 149 jts. R/U Pwr Swl SWI

SDFN

Load out and travel from 7-2-4-1w

280# SIP, RU PERFORATORS W/L RIH SET KILL PLUG @ 4690' POOH BLEED WELL DWN AND PREFORM 30-MIN. NEG. TEST (GOOD) RD WIRE LINE

MIRUSU

N/D 5K FMC FRAC VALVE, N/U WTD DOUBLE 2-7/8 PIE RAM BOPE

R/U 4G TESTERS PT CHAMBERS ON BOP TO 3000# ALL HELD, P/T ALL COMPONENTS OF BOPE 250 LOW FOR 5-MIN. AND 5000# HIGH FOR 10-MIN. (ALL TESTS GOOD)

R/U WORK FLOOR PREP AND TALLY TBG. P/U RIH W/ 4-3/4 CHOMP MILL FOLLOWED BY 149 JTS. 2-7/8 J-55 TBG. R/U PWR SWL EOT @ 4630' SWI

Crew Travel

SDFN

SWI

SDFN

Crew Travel

PUMP 15 BBLs DOWN TBG CONT TIH W/ TBG TAG PLUG @ 4690 RU GRACO POWER SWIVEL DRILL OUT PLUG 15 MIN

CONT PU & TIH TAG FILL @ 4779' CLEAN OUT 151' OF FILL TO PLUG @ 4930 DRILL OUT PLUG 22 MIN,



Well Name: GMBU Q-19-8-18

Summary Rig Activity

Start Time	11:30	End Time	14:00	Comment
Start Time	14:00	End Time	17:00	CONT PU & TIH TAG FILL @ 5862 CLEAN OUT 208' OF FILL TO PLUG @ 6070' CIRC WELL CLEAN, DRILL OUT PLUG 19 MIN
Start Time	17:00	End Time	18:00	WELL WENT ON A VAC, PUMP 45 BBLS TO REGAIN CIRC, CONT PU & TIH TAG FILL @ 6520' CLEAN OUT 120' OF FILL TO PBTD @ 6640' CIRC WELL CLEAN, RACK OUT DRILL EQUIP
Start Time	18:00	End Time	19:00	LD EXTRA TBG DRAIN PUMP AND EQUIP, SWIFN
Start Time	19:00	End Time	00:00	Crew Travel
Start Time	00:00	End Time	00:00	SDFN
Report Start Date	12/20/2013	Report End Date	12/21/2013	24hr Activity Summary
Start Time	00:00	End Time	06:00	POOH w/ tbg. N/D BOP N/U wellhead, change over to rod equip. P/U and start in hole w/ pump & rods
Start Time	06:00	End Time	07:00	SDFN
Start Time	07:00	End Time	08:30	Crew Travel
Start Time	08:30	End Time	10:15	CHK PRESS ON WELL CSG & TBG ON VAC, R/U PUMP & EQUIP CIRC WELL CLEAN W/ 180 BBLS
Start Time	10:15	End Time	12:00	TOOH W/ TBG LD CHOMP BIT & BIT SUB
Start Time	12:00	End Time	13:30	PU & RIH W/ PROD. BHA & TBG AS FOLLOWS NC, 2 JTS, PSN, 2 JTS, TAC, 198 JTS, LAND TBG ON TBG HANGER
Start Time	13:30	End Time	17:00	ND BOPS & BLIND RAMS, SET TAC W/ 18K TENSION LAND TBG W/ TBG HANGER, NU B-1 ADAPTOR FLANGE W/ TAC @ 6161.57, PSN @ 6216.90, EOT @ 6279.91 X-OVER TO ROD EQUIP
Start Time	17:00	End Time	18:00	PREP RODS, PU & PRIME CENTRAL HYD 25-175-RHAC-20-4-21-24 PUMP W/ 224 MAX STROKE, PU & TIH W/ RODS AS FOLLOWS 30-7/8 8 PER, 115- 3/4 4 PER RODS R/U POL, RODS P/U AND SWI
Start Time	18:00	End Time	19:00	DRAIN PUMP & EQUIP & TARP UP WELL
Start Time	19:00	End Time	00:00	Crew Travel
Report Start Date	12/23/2013	Report End Date	12/24/2013	24hr Activity Summary
Start Time	00:00	End Time	06:00	Cont. in hole w/ rods test pump & tbg. hang off well RDSU and move onto the A-25
Start Time	06:00	End Time	07:00	SDFN
Start Time	07:00	End Time	10:30	Crew Travel
Start Time		End Time		CHK PRESS ON WELL 360 CSG, TBG DEAD. CONT PU & TIH W/ RODS AS FOLLOWS CENT HYD 2 1/2 X 1 3/4 X 24' RHAC PUMP, 30 7/8 8-PER, 115 3/4 4-PER, 103 7/8 4-PER, 1 1/2 X 30' POLISH ROD, SEAT PUMP, RU PUMPING UNIT FILL TBG W/ 4 BBLS STROKE PUMP W/ UNIT TO 800 PSI (GOOD)

NEWFIELD



Well Name: GMBU Q-19-8-18

Summary Rig Activity

--	--	--	--

Start Time	End Time	Comment
------------	----------	---------

10:30	11:30	RDSU, move over to A-25-8-17
-------	-------	------------------------------

--	--	--